
Rapid Antiproton Transfers

Elvin Harms
Temple Review
July 1, 2003

Rapid Antiproton Transfers

- Introduction
- Overview of Each Subproject
 - Beam Line Regulation
 - Software
 - Oscillation Feedback & Control
 - Diagnostics
 - Commissioning
- Summary

Rapid Antiproton Transfers - Introduction

- Current set-up time
 - ~2 hours to load the Tevatron
 - ~1 hour to set up and send pbars to the Recycler
- Motivation for speeding process
 - Increased stacking rates only possible by not building a core - empty the Accumulator when it 'fills up'
 - Maintain as high an average stacking rate as possible - minimal impact on stacking
- Expected set-up time
 - move from shot set up to 'transfers on event'
 - actually, automatic transfers, they occur on event now
 - Unstack/transfer time now ~30 seconds, driven by time to adiabatically bunch, accelerate, and extract pbars from the Accumulator

Rapid Antiproton Transfers - Beam Line Regulation

- Motivation
 - Current AP1 powering scheme - 2 sets of power supplies
 - Ramp beam line on clock events - single set of supplies
- 1.3.6.2.1 Magnetic Field Tolerance
 - Current bi-modal scheme recognized power supply limitations
 - Reverse engineer what regulation is really needed
- 1.3.6.2.2/3 Improve regulation as necessary
 - Preliminary look indicates current regulation may be sufficient
- 1.3.6.2.4 Waveform generator control for AP1
 - standard Fermilab CAMAC cards can be build to support ramping AP1 supplies
 - 15 cards needed at \$800 each
 - Can be fabricated and installed in a matter of weeks

Rapid Antiproton Transfers - Software



- 1.3.6.3.2 Support for beam line ramping
 - User friendlier 465 card application
- 1.3.6.3.3 Orbit correction
 - Reverse proton tune-up no longer occurs except as transfer performance dictates
 - Application needed to read/use beam line BPM data for pbars to make corrections
- 1.3.6.3.4 Lattice measurement
 - Parasitic/rapid beam measurements of beam line lattice will be needed
- 1.3.6.3.1, 6 Sequencer upgrades/other support
 - Next generation sequencer will be required
 - Preliminary work in progress
 - Other new software undoubtedly needed

- 1.3.6.4.1 Pbar Injection damper in MI
 - Work in progress by Bill Foster, et al
 - Demonstrated with protons
 - Hardware procured - reversing switches
 - People identified
 - Current specification - damp 1mm distortion in 10 turns
- 1.3.6.4.2 Quadrupole pickup in Accumulator
 - Feasibility studies in progress

Rapid Antiproton Transfers - Diagnostics

- 1.3.6.5.1 Beam line BPM upgrade
 - no routine reverse proton tuneup
 - no Pbar beam line BPM data - intensity too low, bunch structure?
 - outdated processors
- 1.3.6.5.2 Magnetic field probes on beam line elements
 - Proof of principle in progress on a quadrupole
 - easy to install, place into operation (1 day)
 - ~\$1500/unit, up to 130 units required (all beam line elements)
 - Identifying critical magnets to instrument

Rapid Antiproton Transfers - Diagnostics



Proof of principle - beam line quadrupole Hall probe

Rapid Antiproton Transfers - Commissioning


- Phased approach
 - Implement aspects which will benefit Collider operation in short term
 - Complete additional steps in anticipation of Recycler integration

Rapid Antiproton Transfers - Resources

WBS	Subproject	In Charge	Finish Date	M&S Est	M&S Cont
1.3.3	Pbar Stacking and Cooling	Dave McGinnis	11/17/05	\$2,254,000.00	46%
1.3.3.1	Stacking and Cooling Integration	Dave McGinnis	11/4/05	\$0.00	
1.3.3.2	Debuncher Cooling	Paul Derwent	6/2/03	\$0.00	
1.3.3.3	Stacktail Cooling	Paul Derwent	11/17/05	\$1,171,000.00	40%
1.3.3.3.1	Momentum	Paul Derwent	11/17/05	\$1,004,000.00	40%
1.3.3.3.2	Betatron	Paul Derwent	11/17/05	\$167,000.00	40%
1.3.3.4	Recycler Stacking and Cooling	Sergei Nagaitsev	4/8/05	\$0.00	
1.3.3.5	Electron Cooling	Sergei Nagaitsev	1/25/05	\$566,000.00	44%
1.3.3.5.1	Commission Full Beamline	Sergei Nagaitsev	3/19/04	\$55,000.00	45%
1.3.3.5.2	Design and procure components	Jerry Leibfritz/Sergei Na	1/30/04	\$373,000.00	42%
1.3.3.5.3	Disassemble Wideband Facility	Jerry Leibfritz/Sergei Na	6/1/04	\$22,000.00	58%
1.3.3.5.4	Transport Components to MI-31	Jerry Leibfritz	7/27/04	\$24,000.00	60%
1.3.3.5.5	Install Pelletron at MI-31	Jerry Leibfritz/Sergei Na	8/10/04	\$37,000.00	60%
1.3.3.5.6	Commission Pelletron	Sergei Nagaitsev	10/19/04	\$0.00	
1.3.3.5.7	Install E-Cool Transferline	Jerry Leibfritz	8/27/04	\$23,000.00	40%
1.3.3.5.8	Modifications to MI/RR	Jerry Leibfritz	9/18/03	\$15,000.00	40%
1.3.3.5.9	Install Cooling Section in RR	Jerry Leibfritz/Sergei Na	9/6/04	\$17,000.00	40%
1.3.3.5.10	Commission Cooling Section	Sergei Nagaitsev	9/23/04	\$0.00	
1.3.3.5.11	Commission Electron Cooling	Sergei Nagaitsev	1/25/05	\$0.00	
1.3.3.6	Rapid Transfers	E Harms	5/5/05	\$517,000.00	60%
1.3.3.6.1	Document Fast Transfer scheme	E Harms	4/21/03	\$0.00	
1.3.3.6.2	Beam Line Regulation	E Harms	2/13/04	\$12,000.00	40%
1.3.3.6.3	RT Software	E Harms	3/4/05	\$0.00	
1.3.3.6.4	Oscillation Feedback and Control	B Foster	1/9/04	\$0.00	
1.3.3.6.5	Diagnostics	E Harms	12/16/04	\$505,000.00	60%
1.3.3.6.6	Commission Fast Transfers	E Harms	5/5/05	\$0.00	

Rapid Antiproton Transfers - Resources

1.3.6	Rapid Transfers		Wed 1/1/03	492 days?	\$0.00	
1.3.6.1	Document Fast Transfer scheme		Tue 4/1/03	15 days	\$0.00	B
1.3.6.2	Beam Line Regulation		Tue 4/1/03	68 days	\$0.00	
1.3.6.2.1	Determine magnetic field tolerance		Tue 4/1/03	5 days	\$0.00	C
1.3.6.2.2	Measure and improve power supply reg		Tue 4/8/03	25 days	\$0.00	C 444
1.3.6.2.3	Ramp waveform control of AP1		Tue 5/13/03	38 days	\$0.00	
1.3.6.2.3.1	Build new 465 cards		Tue 5/13/03	33 days	\$12,000.00	B 445
1.3.6.2.3.2	Install and commission new 465 ca		Thu 6/26/03	5 days	\$0.00	B 447
1.3.6.3	RT Software		Tue 4/22/03	340 days	\$0.00	
1.3.6.3.1	Streamline Sequencer		Tue 4/22/03	10 days	\$0.00	B 442
1.3.6.3.2	465 card application		Tue 5/6/03	60 days	\$0.00	B 450
1.3.6.3.3	Orbit Correction		Tue 7/29/03	90 days	\$0.00	B 448,451
1.3.6.3.4	Lattice measurement		Tue 12/2/03	90 days	\$0.00	B 452
1.3.6.3.5	TBT correction		Tue 4/6/04	90 days	\$0.00	B 453
1.3.6.3.6	RT: other software		Thu 8/28/03	240 days	\$0.00	B 451FS+22 days
1.3.6.4	Oscillation Feedback and Control		Wed 1/1/03	438 days?	\$0.00	
1.3.6.4.1	MI Injection Damper		Tue 4/22/03	359 days	\$0.00	
1.3.6.4.1.1	Specify necessary damper voltage		Tue 4/22/03	20 days	\$0.00	C 442
1.3.6.4.1.2	Determine scope of work		Tue 5/20/03	20 days	\$0.00	C 458
1.3.6.4.1.3	Purchase load switches/power amp		Tue 6/17/03	2 days	\$0.00	B 459
1.3.6.4.1.4	Specify and fabricate damper picku		Thu 6/19/03	180 days	\$0.00	C 460
1.3.6.4.1.5	Specify, design, and build low level		Thu 6/19/03	240 days	\$0.00	C 460
1.3.6.4.1.6	Install damper system		Mon 7/26/04	20 days	\$0.00	B 461,462,557SS
1.3.6.4.1.7	Test low level		Mon 8/23/04	10 days	\$0.00	B 463
1.3.6.4.2	Accumulator Quad pickup	? Nagaslaev	Wed 1/1/03	1 day?	\$0.00	C
1.3.6.5	Diagnostics		Tue 4/1/03	240 days	\$0.00	
1.3.6.5.1	P1, P2, AP1, AP3 53 MHz BPM upgrad		Tue 4/1/03	240 days	\$500,000.00	C
1.3.6.6	Commission Fast Transfers		Fri 9/17/04	44 days	\$0.00	C 454,455,464,467,557
1.3.6.7	Rapid Transfers Operational (Milestone)		Thu 11/18/04	0 days	\$0.00	468



Rapid Antiproton Transfers - Summary

- With the Recycler integrated into Collider operation and high stacking rates, rapid transfers will be vital
 - Unstack and transfer every 30 minutes
 - Interrupt stacking for 1 minute
- 5-fold plan to realize rapid transfers
 - Beam Line Regulation
 - Software
 - Oscillation Feedback & Control
 - Diagnostics
 - Commissioning
- Work begun in some areas, more just around the corner