
Run II Upgrades

DOE mini-review

September 8, 2004
Jeff Spalding

Contents

- Introduction:
 - The Run II Upgrade Plan and Resource-Loaded Schedule
- Version 3
 - Major changes from v2 (Feb DOE Review)
- Recommendations Scorecard from Feb DOE Review
- Context for the next talks

Goal: maximize the integrated luminosity delivered

- Peak luminosity

$$\mathcal{L} = \frac{3\gamma f_0}{\beta^*} (BN_p) \left(\frac{N_p}{\varepsilon_p} \right) \frac{F(\beta^*, \theta_{x,y}, \varepsilon_p, \bar{\varepsilon}_p, \sigma_{p,\bar{p}}^L)}{(1 + \varepsilon_{\bar{p}} / \varepsilon_p)}$$

Emittances $\varepsilon_p, \varepsilon_{pbar}$, form factor F , β^* provide some gains

But major improvements from bunch intensities

- especially total number of pbars BN_{pbar} ,
- proton brightness (N_p/ε_p) is constrained by beam-beam tune shift

- Luminosity lifetime (tunes, beam-beam interactions)
- Reliable operation - an essential component, major gains in the last year



Address all via operational improvements
and upgrade projects

Run II Upgrade Plan - RLS

The Run II Upgrade Plan is dynamic

- via built-in scope decision points
- scope/strategy updates from operations or project R&D

Emphasis

- Increase pbar production, stack rate and size
 - Slip stacking: double intensity on pbar production target
 - Pbar acceptance upgrade
 - Stacking rate and stack size (stacktail, Recycler, e-cooling)
- Upgrade Tevatron for higher bunch intensities
 - Helix
 - R&D on active beam-beam compensation

Also

- Many significant instrumentation upgrades (BPMs, BLMs, IPM...), alignment (Tevatron), reliability improvements (Tev Abort System...), and vulnerabilities (Linac tubes, Tev stands...)

WBS captures all long-term work planned for Run II

v1→v2→v3

- V1 (July 03)
 - July 03 DOE Review
 - Guesstimate for Recycler and Electron Cooling
 - Scheduled technical reviews and scope decisions
 - Developed Operating Phases, and Design and Base projections
- V2 (Feb 04)
 - Feb 04 DOE
 - Recycler plan detailed - fitted within the place-holder schedule!
 - Many scope decisions made
 - More schedule and resource detail
 - Design, Base and Fall-back scenario analysis
- V3 (July 04)
 - Schedule changes - re-optimize strategy to compensate
 - Minor scope changes and ADD new instrumentation subprojects within budget guidance
 - No significant change in long-term Design projection, Fall-back more robust


CR doc's

1-8

9-21

Subprojects and Operating Phases


V2: Feb 04 Review



No internal schedule contingency in the RLS (intended for planning, not reporting)
Contingency at top level add ~3 months (Phase 2), 6 months each (other phases)

Subprojects and Operating Phases

V2: Feb 04 Review



Top level milestones
- start of each phase

Schedule & Strategy Update
in version 3

Operating Phases

→ drive luminosity projection

No internal schedule contingency in the RLS (for planning, not reporting)
Contingency at top level add ~3 months (Phase 2), 6 months each (other phases)

Class A Milestones: v2 and v3

Milestone	V2	V3
New target in operation	1/2/04	1/2/04
Review Recycler commissioning plan	2/9/04	3/1/04
Recycler commissioned for Electron cooling	6/1/04	6/1/04
Beam Sweeping ready	8/25/04	10/21/04
Initial AP2&DB improvements complete	11/22/04	11/22/04
New standard separators operational	10/25/04	12/16/04
Slip Stacking operational	12/23/04	12/23/04
Start Phase 2	12/23/04	12/23/04
New lens operational	6/10/05	8/25/05
Electron cooling of pbars demonstrated	6/1/05	9/8/05
Intermediate AP2&DB improvements complete	10/3/05	10/3/05
Rapid Transfers operational	6/14/05	10/31/05
Start Phase 3	6/1/05	1/2/06
Final AP2&DB improvements complete	10/2/06	10/2/06
Stacktail Upgrade: Bandwidth, operational	12/6/05	12/5/06
Start Phase 4	12/6/05	12/5/06
New helix operational	12/5/06	12/14/06
TEL system operational	2/12/07	2/12/07
Start Phase 5	2/12/07	2/12/07

demonstrate
e-cooling

Phase 3 redefined:
now includes interim
stacktail upgd

stacktail
bandwidth
upgrade

Schedule and Strategy Update

- E-cooling
 - R&D program on e-beam completed successfully
 - now installing at Recycler - on plan
 - Schedule slip 3 months vs V2
 - change to upgrade schedule, but NOT BAD for such a challenging R&D project
 - Next: Commission electron cooling of pbars at Recycler
 - schedule uncertain, est demo of cooling by 05 shutdown, start in HEP by end 05
 - Two recent technical reviews:
 - e-cool installation (7/27/04), and commissioning plan (8/10/04)
 - Need operating experience with electron cooling before installing the bandwidth upgrade in the Stacktail
 - now scheduled for 06 shutdown
- Mixed source operation (pbars from both Accumulator and Recycler) until e-cooling phased into operation - capitalize on improved reliability
- Phased approach to the Stacktail Upgrade

Phased Approach

Stacktail

- Present stacktail
 - average $\sim 10E10/\text{hr}$, core $< 250E10$ in the accumulator
- Tank move
 - $\sim 30E10/\text{hr}$ (plus $\times 2$ margin), core $\sim 40\text{--}60E10$, transfer $>$ hourly to Recycler
 - quick to implement and reverse
- Bandwidth upgrade
 - $\sim 40E10/\text{hr}$ ($\times 2$ margin), core $\sim 20\text{--}40E10$, transfer \sim half-hourly
 - major shutdown to install and reverse


Accumulator \rightarrow Recycler Transfers

- now: manual, proton tune-up like shot setup, takes < 1 hr
- Mar 05: MI injection dampers, AP1 ramped, no tune-up $\sim 10\text{min}$
- Dec 05: BPM upgrade \rightarrow auto-feedback for next transfer $\sim 2\text{min}$

Sequence


- mixed-source operation through 05
- end 05 (once electron cooling is operating in HEP): Tank move
- early 06: Bandwidth upgrade ready to install
- bandwidth upgrade installed summer 06 shutdown

Design Projection



- V3 schedule
- Mixed-source operation in 05, assumed to be break-even (conservative)
- Phased stacktail upgrade
- Pbar tax in FY05 (e-cool...)
- More conservative shutdown recovery and learning slope for each phase
- Parameters rounded (store length, HEP hrs)

Design Projection



V2 → V3 Cost Comparison

V2 and V3 M&S and SWF base estimates in \$FY03 (not esc)

\$K in FY03 \$	M&S				SWF			
	Base	Cont		Total	Base	Cont		Total
V1	14,965	7,462	50%	22,427	18,194	9,706	53%	27,900
V2	16,811				17,980			
V3	17,856				19,605			

- Increase V3-V2 is \$1,045K M&S and \$1,625K SWF
- Includes new instrumentation projects (OTR, BLM upgrades)
- Base+contingency in V1 → the budget guidance - manage the work to within this guidance (see later talk)
- Current available contingency is 50% of remaining cost (see later talk)

V2→V3 Change Requests

Log# (#1-8 were v1→v2)

- sched & strategy {
 - 9. Change in schedule and cost for electron cooling and the start of operating phase 3
 - 10. Change in implementation and cost of the Accumulator Stacktail upgrade and operating phases 3 and 4
- 11. Change in scope of the Beam Sweeping subproject
- new inst'n projects → 12. Addition of subproject to build optical transition radiation detectors
- 13. Cost change for the helix/separator work plan
- 14. Reduction in scope of AP2 and Debuncher acceptance work plan
- 15. Cost re-estimate for the Tevatron Beam Loss Monitor (BLM) upgrade and addition of subprojects for Main Injector and Booster BLM systems
- 16. Reduction in scope for specific tasks in Recycler commissioning
- 17. Increase in cost for general alignment support during Shutdowns
- 18. Labor cost increase for Transfer-line BPM upgrade project
- 19. Labor cost increase for Tevatron BPM project
- 20. Labor cost increase for Tevatron Alignment in '04
- 21. Labor cost increase for the LINAC tubes project

The total cost change in these documents is \$852K M&S and \$1645K labor

Recommendations Score Card

- 26 recommendations from Feb DOE review
- Compiled in a "recommendations scorecard" - see handout
- Will not go through in detail here ...

Status Summary →

- Many items were already on-going
- "In-process" recommendations will be carried out by next review

	Recommendation	Carried out	In Process	As recommended	Similar to Rec'n
Accelerator Physics	AP1		X		X
	AP2		X		X
Proton Source	PS1=AS3	X		X	
	PS2	X		X	
	PS3	X		X	
	PS4	X		X	
Antiproton Source	AS1	X		X	
	AS2=I1	X		X	
	AS3=PS1	X		X	
	AS4	X		X	
	AS5	X		X	
	AS6	X		X	
Tevatron	T1	X		X	
	T2		X	X	
	T3		X	X	
	T4		X		X
	T5		X		X
	T6		X	X	
	T7		X	X	
Instrumentation	I1=AS2		X	X	
	I2	X		X	
Cost Estimate	CE1	X		X	
Overall Management	OM1		X		X
	OM2=MP1	X		X	
Management Process	MP1=OM2	X		X	
Planning and Plans	PP1	X		X	
	PP2	X		X	
	PP3	X		X	
	PP4	X		X	

Next Talks

- Dave McGinnis
 - Operational improvements
 - Performance since Feb review > design projection
 - Mixed-source operation
 - Pbar stacking rate
- Pushpa Bhat
 - Excellent technical progress on the upgrade projects
 - Technical reviews
- Jeff Spalding
 - Schedule and cost report
 - Luminosity projection: fall-back scenario